The 12th OCPA Accelerator School (OCPA2025)

Accelerator Facilities of the University of Science and Technology of China (USTC)

Guangyao Feng, Zhenghe Bai

National Synchrotron Radiation Laboratory (NSRL) University of Science and Technology of China (USTC)





Outline

- **□** Introduction of USTC and NSRL
- ☐ Hefei light source (HLS-II) at NSRL
- ☐ Project of Hefei Advanced Light Facility (HALF)
- **□** Summary



Introduction of USTC

- USTC was established by the Chinese Academy of Sciences (CAS) in 1958.
- ☐ In 1970, USTC moved from Beijing to its current location in Hefei, the capital of Anhui Province.
- Focusing on exploring new frontiers in science and nurturing young talents with global perspectives, it serves the nation as an innovator in quality education and scientific research.





Introduction of USTC

- ☐ In 1978, USTC set up the country's first "Special Class for the Gifted Young" and the first graduate school.
- USTC is also the only university that operates two national laboratories on campus: the National Synchrotron Radiation Laboratory (NSRL) and the Hefei National Laboratory for Physical Sciences at the Microscale (HFNL).
- At present, the University is home to 16245 students and 2050 faculty members, and offers customizable programs and extracurricular activities to all the students.






Synchrotron Radiation Light Source


□ Synchrotron Radiation


Probe to Explore the Microstructure of Materials

□ High quality electromagnetic radiation

- Very broad and continuous spectral range from infrared up to the hard x-ray region
- High degree of collimation of the radiation
- High degree of polarization
- Natural narrow angular collimation
- High flux
- High brightness
- Pulsed time structure
- High beam stability
- All properties quantitatively evaluable









National Synchrotron Radiation Laboratory (NSRL)

National Synchrotron Radiation Lab. (NSRL)

☐ The First National Lab. in China (1983)


Hefei Light Source (HLS)

■ The First Dedicated Synchrotron Radiation User Facility in China (1989)









Phase II (1998-2004)





Major Upgrade (2009-2014)






2009-2014 Full re-construction

- accelerator (Linac injector, Storage ring)
- 5 beamlines and experimentalstations

2016-2018 Upgrading

- power supply system upgrade
- performance improvement of beamlines and end-stations
- 10 beamlines
- top-off operation mode (July,2018)










Full Energy Linac Injector in the Tunnel

Main Parameters of the Full-energy Linac

Energy	800 MeV
Microwave frequency	2856 MHz
Bunch charge	1 nC
Vertical emittance	< 60 π mm∙ rad
Horizontal emittance	$< 60 \pi mm \cdot rad$
Repetition rate	1 Hz
Energy spread (rms)	0.5%

- The linac mainly consists of an electron gun and 9 acceleration sections.
- The gun is a traditional DC one with a thermal cathode. The outgoing electron beam has a macro pulse length of 1 ns and bunch charge of about 2 nC.
- After going through a pre-buncher and buncher, the electron beam bunch length turns into 10 ps.
- Each acceleration section includes two 3-meter S-band accelerating tubes which work with the traveling-wave mode. After traversing the accelerating structures, the electron beam is accelerated to 800 MeV.
- A switch magnet is installed at the end of the linac. Using this magnet, the electron beam can be delivered to either the energy spectrum analysis system, or the transport line for the injection of the storage ring.





Optics Functions of One Super Period of the Ring



Magnet Components of the Ring

Main Parameters of the Storage Ring

Beam energy	800 MeV
Circumference	66.13 m
Harmonic number	45
RF frequency	204 MHz
Beam emittance	38 nm∙ rad
Cells	4, DBA Lattice with 2 straight sections per cell (4.0 m+ 2.3 m)
Transverse tunes (H, V)	(4.44, 2.35)
Orbit stability	2 μm


- After the upgrade project, the lattice of the HLS-II storage ring was changed from TBA to DBA type to reduce its emittance to 38 nm·rad and increase the number of straight sections to 8 while remaining the same circumference.
- The storage ring is comprised of 8 bending magnets, 32 quadrupoles and 32 sextupoles with multi-functions (skew quadrupoles and orbit correctors).
- Two straight sections are used for the installation of the RF cavities and for beam injection system, respectively.
- The other straights are installed with six insertion devices, including two elliptically polarizing undulators (EPU), a quasi-period undulator (QPU), an In-vacuum Undulator (IVU), a planar undulator and a wiggler.



Operation of Light Sources in 2024

- 400mA Top-off operation
- Beam Current stability: ±1%
- **Availability: 99.46%**
- Running time per year: 7117.39 h
- Duration of experiments: ~ 177.25 h





- 11 end stations, focusing on the research of quantum materials, catalytic science, bioscience, etc.
- More than 1000 users every year
- More than 400 user publications every year



With development of science and technology, synchrotron radiation users put forward higher requirements for the quality of light sources

- Spatial and temporal resolution
- Experiment completion efficiency
- Stability of light source
- □ Operation for more users
- **□** ...



Higher flux, higher brightness, higher coherence, more insertion devices, advanced technologies in particle accelerator field,...



The fourth generation light source based on diffraction limited storage ring



Flux, Brightness and Coherence


$$\begin{aligned} \textit{Flux} &= \frac{N_{ph}}{\Delta T \cdot \Delta \omega / \omega} \; , \qquad \textit{Brightness} = \frac{Flux}{4\pi^2 \Sigma_x \Sigma_{x'} \Sigma_y \Sigma_{y'}} \; , \qquad f = \frac{\lambda^2 / (4\pi)^2}{\Sigma_x \Sigma_{x'} \Sigma_y \Sigma_{y'}} \\ &\Sigma_{x,y} = \sqrt{\sigma_{x,y}^2 + \sigma_{ph}^2} \; , \quad \Sigma'_{x,y} = \sqrt{\sigma'_{x,y}^2 + \sigma'_{ph}^2} \\ &\sigma_x = \sqrt{\varepsilon_{x} \cdot \beta_x + \sigma_E^2 \cdot \eta_x^2} \; , \quad \sigma'_x = \sqrt{\varepsilon_{x} \cdot \gamma_x + \sigma_E^2 \cdot \eta_x'^2} \; , \quad \sigma_y = \sqrt{\varepsilon_{y} \cdot \beta_y} \; , \quad \sigma'_y = \sqrt{\varepsilon_{y} \cdot \gamma_y} \\ &\sigma_{ph} = \frac{1}{2\pi} \sqrt{\lambda \cdot L} \; , \quad \sigma'_{ph} = \sqrt{\frac{\lambda}{4L}} \end{aligned}$$

X Before reaching the diffraction limit, brightness and coherence of the light source increase significantly with the decrease of beam emittance.

Diffraction limited emittance
$$\varepsilon_{e^-} \le \varepsilon_{ph} = \sigma_{ph} \sigma'_{ph} = \frac{\lambda}{4\pi}$$



Brightness and coherence of the fourth generation light source are 100-1000 times higher than those of the third generation.






Light Sources in Different Energy Regions Address Different Scientific Questions

Hard X-Ray

Structure: Where are the atoms located? How does the atomic structure change?


In-situ observation of complex single crystal growth. Micro scale protein structure. Structural defects in high-temperature alloys ...



VUV Soft X-Ray

Function: State of the electron spin? how it moves, interacts, and reacts?

Chemical reactions (catalysis, combustion), electronic structures (superconductivity, topology), magnetism (spin)...






Advantages of low-energy region light source experimental technology

- Advantages of low-energy light source experimental technology, comparing with medium and high-energy light sources
 - high energy resolution
 - Measurement of Orbital/Spin/Electron/Chemical Valence States
 - Direct measurement of light elements such as C/N/O and 3D elements
- **Examples of synchrotron radiation experiment using low-energy beamlines**
 - High resolution electronic structure measurement (ARPES, RIXS, IR)
 - Spectral and scattering studies of 3D transition metal elements and magnetic materials
 - Unlabeled molecular sensitive imaging of light element materials and life related systems
 - High resolution photoionization experiment
 - High resolution measurement of chemical valence states





Hefei Advanced Light Source (HALF)—Soft X-Ray Diffraction limited Storage Ring Light Source




Scientific Goals of HALF

Accurate Measurement of Electronic States/Chemical States/ Light Element Structures of Complex Systems


Spectroscopy

Multidimensional electronic structure


Imaging/Diffraction
Single particle structure
imaging




mass spectrum




Scanning microscope




nano-ARPES




Stacked imaging




Core level spectroscopy



Coherent diffraction



RIXS/REXS



XPCS



Engineering Goals of HALF

Hefei Advanced Light Facility (HALF)

- Brightness in Soft X-Ray Region $>10^{21}$
- ☐ Coherence in Soft X-Ray Region ~30% (1 keV)
- ☐ Straight sections for IDs > 30

Diffraction Limited Emittance of the Electron Beam

$$\varepsilon_{e^{-}} \le \varepsilon_{ph} = \sigma_{ph} \sigma'_{ph} = \frac{\lambda}{4\pi}$$

Photon Energy / Wave Length	Diffraction Limited Emittance
1.24 keV / 1 nm	100 pm rad

Requirements on the Ring		
Beam Energy	2.2 GeV	
Natural Emittance	<100 pm rad	
Beam Current	350 mA	
Operation Mode	Top off	
Straight Sections	~40	




Technical Challenges of HALF Accelerator

Technical Challenges of the 4th Generation Light Source

- ➤ High Field Gradient, High Quality Magnet Technology
- > Small aperture, High Quality, Combined Function Magnet Technology
- Small Aperture, NEG Coating Vacuum Chamber
- ➤ BPM Technology with Micron Resolution
- High Precision Mechanical Alignment and Positioning of Accelerator and Beam line Assembly
- Six Dimensional Adjustment, High Precision and High Stability Magnet Support Technology
- ➤ Pre-Alignment Positioning Technology on Girder
- ➤ High Stability Solid-state RF Power Source
- ➤ High Performance Insertion Device Technology (Super-Conducting, …)
- **>** ...



Preliminary Research and Development of HALF





Preliminary Research and Development of HALF



Magnetic field measurement device



Septum Magnet



High precision surface detection



Nonlinear Magnet



Magnet Support



D-BPM Processor







Combined Function Magnet



RF Cavity



Power Supply



Monochromator



Vacuum Chamber Coating equipment



Preliminary Research and Development of HALF









Project Process Test has Been Completed in Dec. 2020



In Jan. 2021, the project has passed process acceptance. Test results achieve the design specifications. Some results are better than the design requirements.













The Project Started on June 7th, 2023

Engineering Goals

• Operating in the Low-energy Region. the Fourth Generation Synchrotron Radiation Light Source Based on a Diffraction limited storage Ring

Scientific Goals

• Accurate Measurement of Electronic/ Chemical/ Spin States in Heterogeneous Complex Systems

Construction Contents


• 2.2 GeV Storage Ring with circumference of 480 m. In Phase I, 10 Beamline-Stations will be constructed (capable of accommodating at least 35 beamline-stations)

Project Budget

• 2.77892 billion yuan

Construction Period

• 64 months





Overall Plan and Construction Content

□ Injector

Electron Gun, Pre-injector, Linac and Transport Line

□ Storage Ring


6BA Lattice Structure with 20 Periods, 40 Straight Sections

☐ Optical Beam-Lines and Experimental Stations

10 experimental stations including nano angle resolved photoelectron spectroscopy, medium energy X-ray microscopy imaging, nano space resolved soft X-ray coherent scattering imaging, photoionization mass spectrometry, etc.

□ Public Facilities

Supporting buildings and related power support facilities






Main Parameters of the Injector


Parameters	Design Specification
Beam Energy [GeV]	2.2
Bunch Charge [pC]	300
Beam Emittance [nm rad]	12
Energy Spread (rms)	≤0.2%
Energy Stability (rms)	≤0.1%
Position Error at Injection Point (rms) (dx, dy) [mm]	0.1
Angle Error at Injection Point (rms) (dx _p , dy _p) [mrad]	0.1




Injector of HALF









3D Layout Diagram of the Injector

Partial layout of the Injector





Main Parameters of the Storage Ring

Parameters	Design Specification	
Beam Energy [GeV]	2.2	
Average Beam Current [mA]	350	
Circumference [m]	479.86	
Lattice Structure	6BA	
Natural Emittance of the Beam [pm rad]	86.3	
Beam Orbit Stability (rms)	<10% Transverse Beam Size	
raight Sections 20×5.3 m+20×2.2 m		
Brightness @ 1 keV [Flux/mm ² mrad ²]	1.15×10^{21}	
Coherent fraction of synchrotron emission @ 1 keV	30%	



Storage Ring of HALF






Magnets Distribution along the Ring (6BA)


Elements Distribution at the Straight Sections







Technical Systems of the Storage Ring





Storage Ring Physics - Lattice Design

A modified hybrid 6BA lattice Structure

□ SLS-2 lattice (TME-like cell) + ESRF-EBS lattice (hybrid MBA)


Ultra-low beam emittance + Good nonlinear beam dynamics performance + More straights

- ☐ Effectively shortening the damping time for storage ring with large circumference and low energy
- \square 20 cells. Two straight sections per cell (5.3 m, 2.2 m) \rightarrow 40 straight sections

The ratio of the total length of the straight sections to the circumference of the storage ring is ~32%



Storage Ring Physics - Lattice Design






Storage Ring Physics - Lattice Design

Storage Ring Parameters


Beam Energy	2.2 GeV	
Circumference	479.86 m	
period Number	20	
Natural Emittance	86.3 pm rad	
Tunes (H/V)	48.19/17.19	
Natural Chromaticity (H/V)	-81.6/-56.6	
Momentum Compaction Factor	9.4×10^{-5}	
Damping partition number (H/V/L)	1.36/1.00/1.64	
Damping Time (H/V/L)	28.5/38.8/23.7 ms	
Energy Loss of Bending Magnet Radiation/turn	186.7 keV	
Energy Spread	0.61×10^{-3}	
Number of Straight Sections	40 (5.3 m, 2.2m)	






Storage Ring Physics – Machine Errors and correction

- □ Magnets misalignment: Within girder <30 μm, Between girders <50 μm, roll error <0.1 mrad
- □ Dipole& Quadrupole fractional strength error: <0.05%






BMP (Yellow diamond shape,12), Corrector (Magenta rectangle,12), Girder (Black Box, 6)

☐ Orbit Correction, Optics Correction, Coupling and Dispersion Correction

After Correction

	Closed Orbit Correction in Hor.	Closed Orbit Correction in Ver.	β-beating in Hor.	β-beating in Ver.	Dispersion	
RMS Value	41 μm	53 μm	1.2%	1.1%	0.3 mm	
Max. Value	250 μm	280 μm	3.4%	3.1%	2.0 mm	

□ 6D Dynamic Aperture after Correction: ~7 mm (rms value, in hor.), ~3.0 mm (rms value, in ver.); Meet the requirement of off-axis injection



6D DA after Correction (Taking RF into account)



Storage Ring Physics – Beam Collective Instabilities

☐ Intra-beam scattering effect: Considering bunch lengthening with harmonic cavity, Emittance of 350 mA fully coupled beam ~ 61 pm rad

Taking into account fully coupled beam, 80% beam bunch filling mode, high-order harmonic cavity lengthen the beam bunch, IDs impact and IBS effect.

Conditions	Beam emittance
0 mA	50 pm rad
350 mA	88 pm rad
350 mA + damping wiggler	72 pm rad
350 mA + damping wiggler + IDs	61 pm rad (IDs working)

- Beam life time (10% coupling, Triple elongation, 350 mA), ~5 hours
- **□** Beam instabilities
 - ◆ Longitudinal microwave instability When the RMS bunch length is 2 mm, it will encounter microwave instability, which can be avoided by stretching the beam length
 - ◆ Transverse single bunch instability Chromaticity +3, bunch length 6 mm, threshold exceeds 5 mA, far higher than the target
 - ◆ Impedance wall instability Chromaticity +3, bunch stretching and transverse bunch by bunch feedback system can effectively suppress impedance wall instability
 - ♦ **High order mode instability** The high-order modes of superconducting high-frequency cavities are generally weak, and their instability threshold is higher than the target current
 - ◆ Ion-trapping Instability Non-uniform filling mode and transverse bunch by bunch feedback system will effectively suppress the instability




Storage Ring Physics – IDs effects

IDs (Including Damping Wigglers) effects


Influence of IDs on beam dynamic aperture

IDs cause a decrease of approximately 0.7 mm in the dynamic aperture at the injection section



Single ID impact to beam emittance and energy loss


- Emittance variation -8~5 pm·rad
- Energy loss variation 5~52 keV
- Energy Spread variation -0.8%~15%





Storage Ring Physics – Injection Process Simulation


Off-axis Three-kicker Bump Injection (the layout allows nonlinear kicker injection in the next stage)




Layout of Injection System

Tracking simulation The residual error of the local bump is controlled within ± 5%, and the beam injection efficiency

can reach over 95%.



Injection process in the first 6 turns



Influence of residual errors of the local bump



Injection System

- ☐ Off-axis Three-kicker Bump Injection Mode
- **□** Kicker Magnet with double pipes

Main Parameters of Injection System

Parameter	unit	Septum	Kicker1	Kicker2	Kicker3
Beam Energy	GeV	2.2	2.2	2.2	2.2
Deflection Angle	mrad	174.5	2.376	5.576	3.2
Integral magnetic field	T m	1.28	0.0174	0.041	0.0235
В	Gauss	9843	580	1363	782
Magnet Length	mm	650×2	300	300	300
Gap	mm	8	46	46	46
Bottom width of pulse	μs	60	5.6	5.6	5.6




Injection System

Kicker Magnet with double pipes







Ceramic vacuum chamber coated with titanium film




Cross section of the Kicker Magnet (K1,K3)






Eddy-current septum magnet


Cross section of the Kicker Magnet (K2)



Magnetic field shield



Septum Magnet Prototype





Radio Frequency System

□ 500 MHz Super-Conducting RF Cavity

(Low Power Loss, High Cavity Voltage, Save Space, Efficient HOM Damping, High Q & Large Beam Aperture)


□ 1.5 GHz The 3rd Harmonic Cavity

(Large R/Q, Lengthening Bunch Length, Long Beam Lifetime, Suppression of Beam Collective Instabilities)

Parameter	Unit	Main RF System	The 3 rd Harmonic RF System / passive
RF Frequency	MHz	499.8 ± 0.2	1499.4 ± 0.5
Operation Temperature	K	4.5	4.5
Cavity Material		Niobium	Niobium
Maximum RF Voltage	MV	2	1
Number of Cavities		1	1
Operation Voltage	MV	1.5 $(Q_0 > 5 \times 10^8)$	$0.5 (R/Q<45\Omega)$
Maximum Input Power	kW	140	Passive cavity




Radio Frequency System




Optimization Design of the 500 MHz Superconducting Cavity Structure

Superconducting Module







High-order Mode Damper

Simulation of the Power Coupler

Digital Low Level Control System



Radio Frequency System

- ☐ The Manufacturing of Superconducting RF Cavity has been completed
- ☐ The Prototype Development of Solid-state Power Source, Power Coupler, and **High-order Mode Damper has been completed**



Superconducting RF Module




Vertical Testing of the RF Cavity



500MHz/250kW Solid State Power Source










RF and Vacuum Testing of High-power Coupler


High Order Mode Damper Vacuum and Power Testing 43





Magnets of the Ring

- 44 Various types of magnets/Cell, 880 Magnets along the Ring
- **Longitudinal Field Gradient Bending Electromagnet (LGB)**
- High Field Gradient Quadrupole Magnet with High Quality and Small Aperture
- **Combined Function Dipole-Quadrupole Magnet**



















LGB1 (2/cell)

LGB2 (2/cell)

LGB3 (2/cell)

Quadrupole magnet (16/cell)

Combined function magnet (4/cell)


Sextupole (8/cell)

Octupole (2/cell)





Magnetic Field Measurement






Magnetic Field Measurement for LGB with Hall Probe Measuring Device





Distribution of magnetic field along the longitudinal direction

Uniformity of integral field within the good field Region



Magnetic Field Measurement for Quadrupole Magnet


HALF Q1 20231222									
	good field region ±13 mm								
Current A B3/B2 B4/B2 B5/B2 B6/B2 Magnet Center (mm)									
					X0	YO			
40	2. 39E-04	5. 37E-05	6. 12E-05	2. 05E-04	0. 02252	0.00811			
60	2. 37E-04	6. 25E-05	6. 13E-05	1. 77E-04	0. 02326	0. 00706			
80	2. 74E-04	6. 98E-05	4. 59E-05	1. 39E-04	0. 02279	0. 00778			
90	2. 96E-04	6. 64E-05	5. 70E-05	1. 31E-04	0. 02263	0. 00825			
100	3. 42E-04	6. 18E-05	5. 56E-05	8. 32E-05	0.02171	0. 00895			
125	4. 01E-04	5. 63E-05	6. 20E-05	1. 13E-05	0.0196	0. 0051			
140	3. 82E-04	6. 52E-05	5. 98E-05	5. 65E-05	0. 02057	0.0037			

High-order harmonic component
Measurement



Vacuum System

- □ Requirement from High Magnetic Field Gradient → Small Magnetic pole Gap → Small Aperture, NEG Coating Vacuum Chamber (Straight Section, Arc Section, Section with Light Extraction...)
- ☐ Activation, Water Cooling, Photon Absorber, Shielding Impedance corrugated tube






Arc Section


Straight Section with SR Extraction



Vacuum System









Vacuum chamber with variable cross-section and front chamber


Vacuum chamber with equal cross-section and front chamber





Vacuum System











photon absorber


photon absorber



Vacuum Coating Equipment







Installing




Preevacuating



surface pretreatment



Discharge




Disassembling



Vacuum degree: 0.98E-8 Pa







Control System

Beam

system

support

system

system

alignment

Radiation

protection

Insertion

devices

diagnostic

Mechanical

Other Systems of the Storage Ring

Slow interlock response time ~10ms

Orbit feedback system: < 10% beam size

General public annual dose< 0.1 mSv

Resolution of position adjustment is better than 1 µm

The first-order vibration frequency is greater than 55 Hz

Alignment accuracy between girders: <50 µm, 0.1 mrad

Meeting requirements of users of ten experimental stations

Alignment/positioning accuracy in girder: <30 µm, 0.1 mrad

Annual radiation dose of staff< 5 mSv, User's annual dose < 1 mSv,

Beam position resolution: 50nm@10Hz, 100nm@10kHz, Beam

Tune resolution: 10⁻⁴; Beam cross-section resolution: better than 2 μm,

Fast interlock response time ~10µs

current resolution: 1 µA

Systems	Function	Main Parameters					
Magnet Power Supply	Providing high-precision and stable excitation current for various types of magnets	Ripple and stability of the main magnet power supply are better than 10 ppm Fast orbit corrector's power supply, small signal bandwidth: 5 kHz					

Realizing remote monitoring and control of various

devices of the storage ring, as well as commissioning

Measuring and diagnosing various beam parameters,

Providing mechanical support for magnets, vacuum

Aligning and installing all online devices in place

Radiation shielding, radiation monitoring, personal

dose

monitoring,

such as beam position, current and emittance, etc.

chambers, beam measurement components, etc.

according to accuracy requirements.

interlock, personal

environmental medium monitoring, etc.

Providing users with synchrotron radiation

and control of the electron beam

Status Mature technology

Mature

technology

Mature

technology

Mature

technology

Mature

technology

Mature

technology

50 lature

technology



Construction Schedule for the Storage Ring

Project Period 64 months

□ Engineering Design	4 months
□ Equipment Processing and Manufacturing	28 months
□ Off-line Testing	6 months
☐ Equipment Installation and On-line Adjustment	12 months
□ Storage Ring Commissioning	8 months
☐ Joint Commissioning with Optical-lines & Experimental	Stations 6 months

Completion of the project Oct. 2018



Current Progress of the Injector

Gridded thermionic DC gun




■ Beam commissioning for the gun have been completed.

ICT calibration

- ☐ Performance parameters meet the design requirements.
- ☐ Process testing has been passed

Traveling wave accelerating structure






- ☐ The first set of process testing has been completed
- High power microwave testing results meet requirements
- Batch production and processing have already started

Solid-state modulator











Vacuum Chamber







Support for accelerating tubes and magnets





component

- Test indicators meet the engineering requirements (10Hz, continuous 72 hours fault-free RF conditioning)
- Process testing of the first modulator has been passed successfully
- Batch production has been started
- The processing and factory \Box testing of the first unit have been completed
- ☐ Batch production has been ☐ Batch production has started
- The processing and factory testing of the first unit have been completed
- been started



Current Progress of the Injector

Magnets and Solenoids











- ☐ All magnets (dipoles, quadrupoles, solenoids, correctors) have been processed and factory tested
- Performance indicators meet engineering requirements

Klystron



Parameters	Technical index	1#
frequency	2856MHz	2856M Hz
Output Power	≥80 MW	80.6
driving power	≤500 W	359
Beam pulse width	≥6.2 μs	6.2
repetition frequency	50 pps	50

5#	

■ All 20 klystrons have been processed and factory tested

BPM detector





	NOMENAL	+700	-TOL	HEAS	DEV	CUTTOL		
4191	0.000	0.050		0.005	8.006	9.000		
PO TASS	4K	Ø 100						
N/C	NOMENAL	1700	100.	HORS	DEV	CARTON		
THIL	0.000	8.000		6.029	8.029	9.000		
内部	@K	1.08 A						
NK.	NOMENAL	+700	-101.	MCAS	DEV	CUTTOL		
THIL	0.000	8.050	0.000	6.032	0.002	9.000		
	98 1	DS1 - TS11 1	F T1812					
AX.	NOMENO	L +70L	-TOL	NEK		DEX	OUTTOL	
	9.800	£.000	-0.839	8.000		4110	-6.130	

■ Mechanical and vacuum performance of the first item meets the standards

Digital low-level RF system

Parameters	Technical index	Measurement result		
Desktop Test: Phase Control Stability	0.02°	0.016°		
Desktop testing: amplitude control stability	0.02%	0.016%		
Online closed-loop: phase control stability	0.2°	0.061°		
Online closed-lor amplitude control st 6-hour closed-loop test results under high power conditions				

- Desktop testing and high-power testing have been completed
- ☐ Performance indicators are better than the design requirements



Current Progress of the Storage Ring

LGB and Quadrupole magnets







LGB1, LGB2 and LGB3



High field gradient quadrupole magnets

☐ Factory tests for All LGB and first batch of the Q, S, O magnets have been completed

Sextupole and Octupole magnets



Girder



■ Performance of the first item of girders meets the requirements

Vacuum system

Four channel coating equipment









■ Solved key issues, including vacuum chamber materials and drawing processes, coating equipment construction and commissioning, VC07 and VC11 section development, etc.



Equipment Offline Commissioning Progress

Construction of high power testing platform for linear accelerator structure has been completed









Magnet offline installation and Commissioning



Installation process verification of the pre-injector section







Through the installation of a high-power testing platform and injector sample section, the installation team was adjusted, initial installation specifications were established, and the consistency between the BIM design of the last line of the injector and the installation effect was verified.

Equipment pre-alignment









Progress of the Construction





Current Status of the Facility Construction





3D rendering

Construction site photo 2025.07.06



Summary

- ☐ The upgraded HLS has reached the advanced level of similar facilities in the world
- The preliminary research and development project of HALF has successfully passed the process test and the process acceptance
- In June 2023, the Hefei Advanced Light Source Project was officially launched. HALF is a low-energy fourth generation synchrotron radiation light source based on a diffraction limited storage ring
- At present, HALF's construction is ongoing, The project is proceeding smoothly according to the plan









